



### GENERAL NOTES:

1. WORK MAY NOT BEGIN WITHOUT FIRST RECEIVING A PERMIT FROM THE VILLAGE OF LOMBARD.
2. THE TRENCH SHALL BE BACKFILLED WITH AGGREGATE (CA-6 GRADATION) AND COMPACTED TO 95% OF THE STANDARD PROCTOR DENSITY. TRENCH SPOIL OR EXCAVATION MATERIAL SHALL BE DISPOSED OF BY THE CONTRACTOR AT THEIR EXPENSE.
3. PRIOR TO THE PLACING OF P.C. CONCRETE, THE EXPOSED EDGES OF ALL EXISTING PAVEMENT SHALL BE SAWCUT FULL DEPTH TO PROVIDE A SMOOTH, CLEAN VERTICAL EDGE, FREE OF LOOSE MATERIAL.
4. EXCAVATIONS SHALL BE PROTECTED BY BARRICADES WITH FLASHING LIGHTS, AT LOCATIONS WHERE ADJUSTMENTS ARE LOCATED IN TRAVEL LANES, A ONE-INCH (1") STEEL PLATE SHALL BE PLACED AND MAINTAINED BY THE CONTRACTOR UNTIL THE SURFACE RESTORATION IS COMPLETE. THE PLATE SHALL BE PROTECTED FROM SLIDING AND TRANSITIONED WITH BITUMINOUS RAMPS AS REQUIRED. BARRICADES AND STEEL PLATES SHALL BE PRESENT AT THE WORK SITE BEFORE EXCAVATION PROCEEDS.
5. MINIMUM WIDTH OF A PATCH SHALL BE FOUR (4) FEET. ALL PATCHES SHALL BE FULL-DEPTH IN A RECTANGULAR SHAPE.
6. STREET OPENINGS SHALL BE RESTORED WITH COLD PATCH BEFORE THE END OF THE DAY AND MAINTAINED UNTIL SUCH TIME AS THE PERMANENT PATCH (CONCRETE OR HOT MIX ASPHALT, DEPENDING ON THE STREET) CAN BE INSTALLED. PERMANENT PAVING MUST TAKE PLACE DURING ACCEPTABLE DAYTIME TEMPERATURE RANGES BETWEEN THE DATES OF APRIL 15 AND NOVEMBER 15.

REV.:	REV.:
REV.:	REV.:
REV.: TEG	REV.: 02-01-2024
DRAWN BY: VJGL	DATE: 02-16-1998

## FLEXIBLE PAVEMENT UTILITY TRENCH

VILLAGE OF LOMBARD
PAVEMENT 11